MR. & MRS. RICHARD WILKINS
JOB # 1122093
Montgomery County
Texas Home Corporation 2005 ©
TILSON
HOME CORPORATION
Family Owned Since 1933
-REVISION-
REVISION - 2/15/12 JS
-PERMITS-
ACC-2/9/2012 JAL
CP-03/19/2012-SS
LP-01/17/2012-GAS
02-5 A
SAN JACINTO
The measurements, dimensions and other specifications shown on this document are guidelines for construction use only. The actual specifications of the finished structure may vary. This document may not be relied on as a representation of what the completed structure will look like
LEGAL DESCRIPTION:
LOT 68, BLOCK 6, SECT 2
OF RIVERWALK
TOTAL LIVING: 2646
COVERED PORCH: 499
GARAGE: 876
UNCOVERED PATIO: 16
RAISE SLAB (1) 2x6 ABOVE NORMAL
ALL BATH VANITIES SINK PROVIDED
AND INSTALLED BY OWNER
NOTE:
5 ¼" BASE BOARDS
3 ¼" DOOR CASING
(DOORS TO BE 6"± FROM
CORNERS WHERE POSSIBLE TO
ALLOW FOR WIDER CASING)
HVAC NOTE:
FRESH AIR INTAKE SHALL BE VENTED THRU GABLE WALL
PLUMBING NOTE:
COOKTOP GAS SHUT-OFF VALVE TO LOCATED IN ADJACENT CABINET
- TOWEL BARS TO BE BLOCKED & MOUNTED @ 54" AFF.
- TOILET PAPER HOLDER TO BE BLOCKED & MOUNTED @ 28" AFF.
- ROBE HOOK TO BE BLOCKED & MOUNTED @ 72" AFF.
- TOWEL RING TO BE BLOCKED & MOUNTED @ 60" AFF.
- SHOWER ROD TO BE BLOCKED & MOUNTED @ 36" ABV. TUB DECK.
WATER HEATER CLOSET NOTES:
WEATHERSTRIP DOOR AND
PROVIDE OUTSIDE COMBUSTIBLE AIR
FLOOR PLAN
Scale: 1/8" = 1'-0"
MASONRY AREA= (63%)